

AC & Bollard FOUNDATION

Conical steel foundation for AC chargers & pedestals

Document No: NI-DS-AC-001-US
Rev: 01 | 2026
Standard: ASCE 7-22 | AISC 360-22 | ACI 318-19
Depth: 550 mm (21,7") standard
Max Wind Rating: 110 mph

PRODUCT OVERVIEW

Conical steel foundation for installation of AC chargers, pedestals, and similar light equipment. Installed without concrete — excavated and backfilled with compacted crushed stone. Bolt-together, no field welding — fully demountable and reusable.

TECHNICAL SPECIFICATIONS

Shell material	(14 GA) ASTM A1011 SS Grade 33
Top section	7.7" × 7.6"
Bottom section	10.5" × 10.5"
Base plate	14.2" × 14.2"
Bolted connection	4 × 5/8" stud bolts, c/c 6"x6"
Assembly method	Laser-cut, kerf-fold hand-formed, pop-riveted
Surface finish	ZM115 per ASTM A1046 — self-healing protection at cut/kerf edges
Weight (foundation)	≈ 8,3 kg (18,39 lbs)
Design basis	ASCE 7–22 IBC 2021 AISC 360-22 (steel) ACI 318-19 (bolts)

INSTALLATION DEPTH & RATED CAPACITY

Burial Depth	Max Equipment Weight	Max Wind Rating (Published)	Calculated Max (Engineering)
550 mm (21,7")	150 kg (330 lbs)	110 mph	137.5 mph*

APPLICATIONS	INCLUDED WITH DELIVERY
- AC Level 2 chargers (3.3–22 kW) - AC charger pedestals - Signage & display screens - Parking payment stations - Traffic signal poles - Lighting pedestals	4 × 5/8" stud bolts 4 × 5/8" nuts + washers - Installation manual reference: NI-MAN-AC-001-US - Material test certificate (mill cert)

INSTALLATION REQUIREMENTS

Backfill material	3/4" crushed stone, compacted
Base course (under foundation)	200 mm (8") compacted crushed stone
Compaction	≥ 95% Proctor per ASTM D698
Tools	Adjustable wrench / torque wrench, spirit level, compactor

RESPONSIBILITY

Nordinfra is responsible for the foundation's structural capacity in accordance with ASCE 7-22 / IBC 2021 / AISC 360-22 / ACI 318-19, as documented in the accompanying structural calculation. The installing contractor is responsible for excavation, backfilling, compaction, and correct assembly. Geotechnical bearing capacity must be verified by the installer or a site-specific geotechnical report for AHJ permit submission.

ALL DIMENSIONS IN INCHES [±0.06"]
UNLESS OTHERWISE SPECIFIED. DO NOT
SCALE DRAWING.

